

## Specification and Procedures

Under the HSDPT Alliance system, it is essential that projects be properly specified, and that procedures be standardized. Some key points:

- Owners or their Representatives must adopt appropriate standardized specifications that allow for proper implementation of dynamic pile testing.
- On-site supervisors need to be provided with a standard check-list for dynamic pile testing.
- PDA testers are required to use standardized field sheets by PDA testers for both manual or electronic entry of data during testing.
- Equipment manufacturers must provide standard testing summary files that can be generated automatically at the end of the test.